



4 SWIVEL CASTERS

Lateral + forward movement for easy positioning



FOLDS COMPACT

Stows to 45 in for transport

PROLIFTCANADA.CA

sales@proliftcanada.ca

(778) 743-4451

Request a quote

Manufactured by K.S.F. · Distributed by Site Handling

- Hand-crank winch with automatic brake — no power needed
- 4 swivel casters for multi-directional movement
- Includes Forks, Pipe Cradle, and Jib Crane attachments

OVERVIEW

The BD2-S is a manual hand-crank material lift for construction and renovation sites. 400 lb (180 kg) capacity, 13 ft (3.96 m) maximum lift height, includes Forks, Pipe Cradle, and Jib Crane attachments. 4 swivel casters let the lifter move laterally as well as forward/backward. Lightweight 130 lb design folds to 45 in stowed height.

SPECIFICATIONS

Model Number	BD2-S
Max Load Capacity	180 kg (400 lbs)
Max Lift Height	3.96 m (13 ft)
Stowed Height	116 cm (45 in)
Weight	60 kg (130 lbs)